

Ref:	ELP/SAI25/Cat-E
Issue:	2A
Date:	11/11/2024

# ELP/SAI25/Cat-E

## Approved Live Working Tasks

---

This document is the property of Network Rail. It shall not be reproduced in whole or part nor disclosed to a third party without the written permission of Network Rail.  
© Copyright 2023 Network Rail.

Uncontrolled copy once printed from its electronic source.

Published and Issued by Network Rail, 2nd Floor, One Eversholt Street, London, NW1 2DN.



## 1 Introduction

This form contains the Electrical Safe System of Work (ESSOW) Category E list of approved tasks for the standard NR/L3/ELP/SAI25/02.

## 2 Approved Live Working Task

Task	Controls
Removing droppers from ground level where the dropper is foul of the line.	<ul style="list-style-type: none"> <li>✓ Conducted where persons remain at least 2.75m from OLE.</li> <li>✓ Only to be completed under Category E – Working on the OLE Live when Route Control has confirmed an Earthed Isolation cannot be achieved.</li> <li>✓ Use of product accepted tools and Live Line insulated poles.</li> <li>✓ Task to be completed in line with Task Risk Control Sheet - NR/L3/MTC/RCS0216/OLE14</li> </ul>
Testing of OLE using approved live line indicators	<ul style="list-style-type: none"> <li>✓ Conducted where persons remain at least 2.75m from OLE.</li> <li>✓ Conducted by staff with Nominated Person (NP) or Authorised Person (AP) competence.</li> <li>✓ Use of product accepted Live Line Indicator and Live Line insulated poles and/or equipment.</li> <li>✓ The Live Working Form is not required to be completed.</li> <li>✓ Testing only in accordance with:               <ul style="list-style-type: none"> <li>○ approved section proving document; or,</li> <li>○ local depot procedure to testing LLIs.</li> </ul> </li> </ul>
Use of live line pole mounted camera	<ul style="list-style-type: none"> <li>✓ Conducted where persons remain at least 2.75m from OLE.</li> <li>✓ Portable cameras shall be used with tested and approved insulated poles</li> <li>✓ Tasks are completed in line with Task Risk Control sheet - NR/L3/MTC/RCS0216/OLE14</li> </ul>
Removal of objects/vegetation from ground level from using live line tools.	<ul style="list-style-type: none"> <li>✓ Conducted where persons remain at least 2.75m from OLE.</li> <li>✓ Only to be completed under Category E – Working on the OLE Live when Route Control has confirmed an Earthed Isolation cannot be achieved.</li> <li>✓ Work in accordance with Task Risk Control Sheet - RCS0216/OLE04 – Removal of objects/vegetation from Live OLE</li> <li>✓ Work in accordance with Task Risk Control Sheet - R/L3/MTC/RCS0216/OLE14</li> </ul>

This document is the property of Network Rail. It shall not be reproduced in whole or part nor disclosed to a third party without the written permission of Network Rail.

© Copyright 2023 Network Rail.

Uncontrolled copy once printed from its electronic source.

Published and Issued by Network Rail, 2nd Floor, One Eversholt Street, London, NW1 2DN.

