

Ref:	NR/L3/ELP/SAI25/Cat-E
Issue:	02
Date:	02 December 2023
Compliance Date:	01 September 2025

NR/L3/ELP/SAI25/Cat-E

Approved Live Working Tasks

This document is the property of Network Rail. It shall not be reproduced in whole or part nor disclosed to a third party without the written permission of Network Rail.
© Copyright 2023 Network Rail.

Uncontrolled copy once printed from its electronic source.

Published and Issued by Network Rail, Waterloo General Office, London, SE1 8SW.



Ref:	NR/L3/ELP/SAI25/Cat-E
Issue:	02
Date:	02 December 2023
Compliance Date:	01 September 2025

1 Introduction

This form contains the Electrical Safe System of Work (ESSOW) Category E list of approved tasks for the standard NR/L3/ELP/SAI25/02.

2 Approved Live Working Task

Task	Controls
Removing droppers from ground level where the dropper is foul of the line.	<ul style="list-style-type: none"> ✓ Conducted where persons remain at least 2.75m from OLE. ✓ Only to be completed under Category E – Working on the OLE Live when Route Control has confirmed an Earthed Isolation cannot be achieved. ✓ Use of product accepted tools and Live Line insulated poles. ✓ Task to be completed in line with Task Risk Control Sheet - NR/L3/MTC/RCS0216/OLE14
Testing of OLE using approved live line indicators	<ul style="list-style-type: none"> ✓ Conducted where persons remain at least 2.75m from OLE. ✓ Conducted by staff with Nominated Person (NP) or Authorised Person (AP) competence. ✓ Use of product accepted Live Line Indicator and Live Line insulated poles and/or equipment. ✓ Testing only in accordance with: <ul style="list-style-type: none"> ○ approved section proving document; or, ○ local depot procedure to testing LLIs.
Use of live line pole mounted camera	<ul style="list-style-type: none"> ✓ Conducted where persons remain at least 2.75m from OLE. ✓ Portable cameras shall be used with tested and approved insulated poles ✓ Tasks are completed in line with Task Risk Control sheet - NR/L3/MTC/RCS0216/OLE14
Removal of objects/vegetation from ground level from using live line tools.	<ul style="list-style-type: none"> ✓ Conducted where persons remain at least 2.75m from OLE. ✓ Only to be completed under Category E – Working on the OLE Live when Route Control has confirmed an Earthed Isolation cannot be achieved. ✓ Work in accordance with Task Risk Control Sheet - RCS0216/OLE04 – Removal of objects/vegetation from Live OLE ✓ Work in accordance with Task Risk Control Sheet - R/L3/MTC/RCS0216/OLE14