

# Mobile Elevated Work Platforms (MEWPs)



## Key Points:

- Must be thoroughly examined, inspected and maintained regularly
- Daily visually check for any defects
- Exclusion zone should be provided under and around the operating area
- Control risk of people or materials falling
- Emergency rescue plans in place and practised
- Competent operators with familiarisation training
- Ensure operation on firm and even ground
- If in use on station platforms work parallel to track



Document No.

SHELT - VS

Date Issued:

14/11/2014

Issue:

V1.0