

Network Rail MK Central 500 Station House Elder Gate Milton Keynes. MK9 1BB Tel: 01908 725863 20<sup>th</sup> March 2013

No: NRS 280

# Network Rail Safety Bulletin

## Use of Log Grabs to Move Rail

#### This bulletin is for the attention of;

Infrastructure Projects; Network Operations; Asset Management; NDS; Principal Contractors; Contractors

#### Issue.

The photograph below depicts new rail being moved using log-grabs. Log-grabs and grapples are **NOT** to be used when lifting new or serviceable rail on Network Rail infrastructure. This activity has been prohibited for several years. Under certain conditions they are permitted to be used to move scrap rail.







Examples of Log Grabs

### Action.

Details of how rail should be handled are set out in NR/L2/RMVP/0200/P005:

Handling new or serviceable rail with road-rail excavator cranes in rail mode (including thimbling) (formerly NR/L2/RMVP/0205)

• Please make sure all staff involved in the planning, supervision and installation of rail are clear on the handling requirements

Network Rail and its contractors could face enforcement action for failing to comply with these requirements

Issued on behalf of: Roan Willmore, Director Safety and Sustainable Development, Infrastructure Projects